



GEORGE MARLTON, JD
PROCUREMENT DIVISION DIRECTOR

PROCUREMENT DIVISION
PUBLIC SERVICES BUILDING
2051 KAEN ROAD | OREGON CITY, OR 97045

REQUEST FOR QUOTES #2017-67
North Clackamas Aquatic Park Floor Renovation and Epoxy Coating
ADDENDUM NUMBER 2
August 24, 2017

On August 17, 2017, Clackamas County (“County”) published Request for Quotes #2017-67 (“RFQ”) and on August 23, 2017 published Addendum #1. The County has found that it is in its interest to amend the RFQ through the issuance of this Addendum #2. Except as expressly amended below, all other terms and conditions of the original RFQ and subsequent Addenda shall remain unchanged.

1. The following items are to be deleted to the Detailed Scope of Work:

- Remove and dispose of CMU cove tiles and prep substrate up to the 1st grout joint and prepare substrate to Tennant ECO Crete Resin Urethane Non-Skid Floor Coating System including moisture vapor.

2. The following items are to be added to the Detailed Scope of Work:

- Remove and dispose of CMU cove tiles and prep substrate up to the 1st CMU grout joint on wall and prepare substrate to accept Tennant ECO Crete Resin Urethane Non-Skid Floor Coating System. Once prepped, apply Tennant ECO Crete Resin Urethane Non-Skid Floor Coating System up to the 1st prepped CMU grout joint on wall covering the areas where cove base was removed and prepped.
- Where ceramic tiles are removed, prep tile removal area substrates to accept Tennant ECO Crete Resin Urethane Non-Skid Floor Coating System. Once prepped apply Tennant ECO Crete Resin Urethane Non-Skid Floor Coating System to all substrate prepared surfaces where tile was removed and prepped.

End of Addendum